



# Island Curb Delineator

## Continuous Ribbon of Reflectivity


The Island Curb Delineator is a low-cost safety solution designed to improve the visibility of raised islands, median noses, pedestrian refuges and roundabouts. The exceptional retro-reflectivity of the 25mm (yellow or white) reflective strip provides a clear visual cue to the motorist thereby reducing accidents and improving safety.

The Island Curb Delineator is made out of 100% polyurethane, the toughest flexible polymer on the market today. It maintains flexibility from  $-20^{\circ}\text{C}$  to over  $70^{\circ}\text{C}$ . The base has pre-cut notches so the delineator can conform (or bend) to meet almost any geometry including straight line, wide arc, narrow arc, or even in a full circle!

\* Increased Visibility

\* Continuous Ribbon of Reflectivity

\* Improved Safety



*Upgraded Roundabout in Wainuiomata, Lower Hutt*

### Features and Benefits

- |   |   |
|---|---|
| - <b>Visible:</b> Continuous ribbon of reflectivity | - <b>Flexible:</b> Notched foot so unit can match curvature     |
| - <b>Simple:</b> Prime, peel & stick application    | - <b>Durable:</b> UV-stable flexible polyurethane for long life |
| - <b>Practical:</b> Low-cost safety solution        | - <b>Versatile:</b> Used on a number of traffic applications    |

### Applications

- |                  |                     |                |                                  |
|------------------|---------------------|----------------|----------------------------------|
| - Raised Islands | - Bridge Approaches | - Roundabouts  | - Pedestrian refuges             |
| - Bull noses     | - Reduced Width     | - Median noses | - Other similar roadway features |



## Technical & Installation

### Applications



As installed in Rangiora, Canterbury



Flexible design for all situations



As installed in Wainuiomata, Lower Hutt

### Installation

The Island Curb Delineator is quick and easy to install.

- Step One:** Factory-applied adhesive strips allow for peel 'n' stick installation.
- Step Two:** A clean, dry surface is required. Sweep or blow off the area where the Island Curb Delineator will be installed using a broom or blowgun to remove any gravel, sand or other debris.
- Step Three:** We recommend that the surface is primed with a spray adhesive for extra grip. The spray adhesive normal requires only one minute of drying time before placement of the marker or delineator.
- Step Four:** Peel off the release paper from the Island Curb Delineator and press the reflectors in place.

### Island Curb Delineator Ordering

For ease of ordering, please mention the Island Curb Delineator and reference the required colour / stock code.

MO25 01 Yellow



MO25 02 White



### Specifications

**Dimensions:**  
 Length: 1200mm  
 Height: 50mm  
 Depth: 30mm

**Reflector:**  
 25mm High

**Slits / Notches:**  
 40mm spacing

