

Island Curb Delineator

Continuous Ribbon of Reflectivity


The Island Curb Delineator is a low-cost safety solution designed to improve the visibility of raised islands, median noses, pedestrian refuges and roundabouts. The exceptional retro-reflectivity of the 25mm (yellow or white) reflective strip provides a clear visual cue to the motorist thereby reducing accidents and improving safety.

The Island Curb Delineator is made out of 100% polyurethane, the toughest flexible polymer on the market today. It maintains flexibility from -20°C to over 70°C . The base has pre-cut notches so the delineator can conform (or bend) to meet almost any geometry including straight line, wide arc, narrow arc, or even in a full circle!

* Increased Visibility

* Continuous Ribbon of Reflectivity

* Improved Safety



Upgraded Roundabout in Wainuiomata, Lower Hutt

Features and Benefits

- | | |
|---|---|
| - Visible: Continuous ribbon of reflectivity | - Flexible: Notched foot so unit can match curvature |
| - Simple: Prime, peel & stick application | - Durable: UV-stable flexible polyurethane for long life |
| - Practical: Low-cost safety solution | - Versatile: Used on a number of traffic applications |

Applications

- | | | | |
|------------------|---------------------|----------------|----------------------------------|
| - Raised Islands | - Bridge Approaches | - Roundabouts | - Pedestrian refuges |
| - Bull noses | - Reduced Width | - Median noses | - Other similar roadway features |

Island Curb Delineator: Call us now to place your order

Technical & Installation

Applications



As installed in Rangiora, Canterbury



Flexible design for all situations



As installed in Wainuiomata, Lower Hutt

Installation

The Island Curb Delineator is quick and easy to install.

- Step One:** Factory-applied adhesive strips allow for peel 'n' stick installation.
- Step Two:** A clean, dry surface is required. Sweep or blow off the area where the Island Curb Delineator will be installed using a broom or blowgun to remove any gravel, sand or other debris.
- Step Three:** We recommend that the surface is primed with a spray adhesive for extra grip. The spray adhesive normal requires only one minute of drying time before placement of the marker or delineator.
- Step Four:** Peel off the release paper from the Island Curb Delineator and press the reflectors in place.

Island Curb Delineator Ordering

For ease of ordering, please mention the Island Curb Delineator and reference the required colour / stock code.

MO25 01 Yellow



MO25 02 White



Specifications

Dimensions:
 Length: 1200mm
 Height: 50mm
 Depth: 30mm

Reflector:
 25mm High

Slits / Notches:
 40mm spacing

